AGENDA COUNCIL COMMITTEE MEETING MUNICIPAL DISTRICT OF PINCHER CREEK JANUARY 9, 2018 9:00 AM

- 1. Approval of Agenda
- 2. Meeting with Alberta Transportation
 - Is Council still wishing to meet with Regional Director Darren Davidson?
- 3. Spring AAMDC Convention
 - Which Councillors plan to attend this event?
- 4. FCM Convention Halifax
 - Which Councillors are wishing to attend?
- 5. Council Picture
 - Decision on Council Picture for Official Purposes required
- 6. Regional Water and Wastewater Discussion Paper Town / MD
 - Dated December 11, 2017
- 7. Beaver Mines Water and Wastewater Project 9:30 am Representatives from MPE will be attending the meeting
- 8. Beaver Mines Wastewater Treatment Report Update
 - Report from Director of Operations, dated January 3, 2018

Committee Jan 9/18

Regional Water and Wastewater Discussion Paper

December 11, 2017

The intent of this discussion paper is to stimulate discussion between the Town of Pincher Creek (Town) and Municipal District of Pincher Creek No. 9 (MD) Councils. Potable water and wastewater services in the region east of the Castle River are exclusively provided by the Town. The MD is looking at how to best provide water and wastewater utility services to the Hamlet of Pincher Station (Hamlet) and at the Pincher Creek Airport (Airport).

Although there have been only a few requests for water and wastewater services in the Hamlet or at the Airport in recent memory, it is felt that there are opportunities for growth that are not possible without the water and wastewater utility services. The Hamlet is situated along the CP Rail line that includes a siding and spur line that could accommodate heavy industrial development, and the Airport, Alberta's seventh longest runway, is the most under-utilized piece of public infrastructure in the region.

There are benefits to both municipalities of providing water and wastewater services to the Hamlet and Airport including attracting and retaining commercial and industrial companies in the region, jobs, tax revenue, and more.

The MD's regional water system, west of the Castle River, is nearing capacity with the recent addition of Beaver Mines and Castle Servicing expansions. Given the Castle River crossing that would be required to service areas in the MD to the east, it is prudent to look at more cost effective options.

By engaging the Town in this initiative, the Town may have the ability to benefit in a more significant way, should additional industrial/commercial companies locate in the region. Although there are a few homes located in the Hamlet, it is felt workers for most significant developments would establish themselves in the Town rather than the Hamlet or MD. Additionally, increases to Airport activity or commercial development, will bring new development, jobs, revenue, including taxes to the region.

Being able to market the region as having water and wastewater services, along the rail line or at the Airport, in the setting of the Crown of the Continent will undoubtedly, attract businesses in the short to mid-term.

- How can the Town and the MD work together to enable water and wastewater services to be expanded into the east Castle River region of the MD?
- Could the Town operate a utility service within the MD?
- What grants are available for this type of project?
- How could new MD tax revenues be shared to recognize the Town's contribution?
- Does the Town water and wastewater systems have the ability to provide for the increased capacity?



Questions for Leo and MPE for Council Committee Meeting Tuesday January 9 -

Discrepancies in Numbers Presented to Date

Some numbers presented in MPE's letter of November 24th and Leo's Memo of Dec 11th don't add up and/or appear to contradict numbers previously provided. Please correct/explain the following discrepancies:

- A. MD portion of the "Beaver Mines Servicing project for pipeline and mechanical components" of \$910,769" (Dec 11 memo) vs. MD's portion of the "Potable Water Transmission Pipeline and Storage" of \$741,029 (Sept 6 memo)
- B. \$3.7 million dollars for the Wastewater Treatment project (Dec 11 memo) vs. updated cost estimate of \$4.9M (Oct 4 email)
- C. Budget Breakdown of \$1.8M for Raw Water Intake (MPE letter Table 1) vs. Projected Cost Breakdown and Funding Breakdowns of \$2.7M each in the same table.
- D. Projected Cost Breakdown of \$6.1M for Regional Supply System (MPE letter Table 2) vs. Budget Breakdown and Funding Breakdown of \$7.6M each in same table.
- E. Cost for Contract 1 Pipeline Construction of \$2.270M for Regional Supply System (MPE letter Table 2) vs. L.W. Dennis low bid of \$2.384M (MPE letter of Sept 1)
- F. Cost for Contract 2 Mechanical (MPE letter sum of both tables) of \$4.587M vs. DMT Mechanical low bid of \$4.816M

Budget and Schedule

I believe Council needs a clearer picture on where we stand with the Project in terms of budget and schedule. Breaking it into 5 subprojects (Leo's Jan 2 memo) is a good start. Thank you for that. Please come to Tuesday's meeting prepared to discuss the following:

- 1. Projected costs including:
 - a. Current vs. original estimates total and by subproject
 - Breakdown of each funder's share including how the Provinces share of costs for Castle
 Water Plan upgrades to the original Project were determined
 - c. An understanding of the accuracy of estimates of various kinds (e.g. "opinions of probable costs" vs. "engineering estimates" vs. "tendered amounts" etc.), since we have a mix
- 2. A detailed schedule including key milestones/decision points
- 3. Checks and balances to ensure successful completion of Project on time and on budget
- 4. Identification of any significant issues or risks which might impact cost or schedule and what are we doing to manage these
- 5. Capacity of system and what additional costs MD will need to incur once that capacity is reached and when that might be expected to occur
- 6. Whatever information you can provide on operating costs I'm not sure we've ever discussed this
- 7. What can we do no improve reporting to Council to ensure we can monitor the progress of the Project going forward

Granting Process

I believe Council would benefit from better understanding of the granting process and how that impacts the MD's portion of the project. In particular:

- 8. What exactly are each of the provincial and federal agencies funding within each of the 5 projects (further to Leo's Jan 2 email)
- 9. When do each of these grants expire?
- 10. How and when do we get the provincial/federal dollars?
- 11. How likely is it that we will get 90% of costs covered from Community Resilience Grant for the \$800K overrun for the water intake project? (Dec 11th memo)
- 12. What are the remaining amounts of the \$9M Federal/Provincial Building Canada Fund Small Communities Fund and how likely is it that these can be used to offset other components of the project (Dec 11th memo)?
- 13. When will we apply for the above and when will we find out?
- 14. When do we apply for grant for wastewater treatment system and when will we find out?
- 15. Do you believe there is still a need for an additional debenture at this time to in light of the answers to the above?

Please ensure Leo/MPE bring all documentation needed to answer the questions above and others that may come up, from myself or other councillors including as a minimum:

- Beaver Mines Water and Sanitary Service Study Nov 2014
- Castle Area Servicing Study Aug 2017
- Beaver Mines Wastewater Options Study Nov 2016
- All information provided by Leo to Council since Sept 1 2017
- MPE Contract
- L.W. Dennis Contract
- DMT Mechanical Contract

TO: Wendy Kay, CAO

FROM: Leo Reedyk, Director of Operations

SUBJECT: Beaver Mines Wastewater Treatment Report Update

1. Origin:

At their September 26, 2017 meeting, Council initiated the Beaver Mines Wastewater Treatment project detailed design work.

2. Background:

MPE Engineering initiated two studies to assist in determining the viability of the proposed site in the SE 19-6-1-W5M, a Historical Resource Impact Assessment and a Phase 1 Geotechnical Evaluation.

The Historical Resource Impact Assessment work done by Arrow Archeology Limited included a site walk about with local land owners and onsite inspection during geotechnical evaluation bore hole and test pit development.

Tetra Tech Canada Inc. performed the Phase 1 Geotechnical Evaluation for the project and provided the attached report for use in the project design. Tetra Tech Canada Inc. has been requested to provide comment on the suitability of a geosynthetic liner given the reported soil conditions; their comments on a liner have not yet been received.

Within their report, Section 5.0, Tetra Tech Canada Inc. indicates that "the site suitability for the proposed sanitary sewage lagoon development is considered low and relocation is highly recommended."

Options for consideration and discussion moving forward include:

- Enter into discussions with the Village of Cowley or the Town of Pincher Creek for use of their lagoon systems;
- Open a request for proposal process for land owners looking to sell suitable land for wastewater treatment in a lagoon and wetland system in close proximity to Beaver Mines;

As previously presented to Council, the *Environmental Protection and Enhancement Act*, Potable Water Regulation requires that:

- "(3) No person shall commence
- (a) the extension of a water distribution system...

Where...

(e) the water distribution system will service a portion of a city, town, specialized municipality, village, summer village, settlement area as defined in the Metis Settlements Act, hamlet, privately owned development, municipal development or industrial development that is not serviced by a wastewater system in respect of which a current approval or registration has been issued under the Act,"

The site at the SE 19-6-1-W5M has been determined to be non-viable, as such, once a decision on the path forward has been made, Alberta Transportation should be notified of the change in the location for Beaver Mines wastewater treatment in the Municipal Districts application with the Alberta Municipal Water Wastewater Partnership grant program.

Following a decision on the path forward, Council is requested to provide direction to Administration.

3. Discussion:

That Council Committee discuss options for Beaver Mines Wastewater Treatment and provide direction to Administration through a resolution in Council.

Respectfully Submitted,

Leo Reedyk

Attachments

Reviewed by: Wendy Kay, Chief Administrative Officer Date: January 1,2018

Leo Reedy .



December 13, 2017

MPE Engineering Ltd.
Suite 300, 714 – 5 Avenue South
Lethbridge, Alberta T1J 0V1

Attention: Mr. Luke Schoening, P.Eng. – Project Manager

Subject: Phase I – Geotechnical Evaluation

Sanitary Sewage Lagoon Development

Beaver Mines, Alberta

1.0 INTRODUCTION

This report presents the results of a geotechnical evaluation, conducted by Tetra Tech Canada Inc. (Tetra Tech), for the proposed sanitary sewage lagoon development to be located near the town of Beaver Mines, Alberta. The site is adjacent to the confluence of the Castle River and Milk Creek at the legal site description of 02-19-06-01 W5M.

The scope of work for this evaluation was outlined in an email proposal issued to Mr. Luke Schoening, of MPE Engineering Ltd. (MPE), on October 26, 2017. The objective of this work was to determine the general subsurface and groundwater conditions, and to provide a site suitability assessment for the proposed sanitary sewage lagoon development.

Authorization to proceed with the work was provided by MPE through a signed Subconsultant Agreement on November 2, 2017.

2.0 SCOPE OF WORK

The scope of work comprised the completion of nine (9) geotechnical boreholes and three (3) testpits across the proposed site. The evaluation also included a laboratory program to assist in classifying the subsurface soils and a summary of soil findings with suitability assessment results.

3.0 GEOTECHNICAL AND LABORATORY WORK

The geotechnical drilling fieldwork for this evaluation was carried out on November 7, 2017, using a track-mounted drill rig contracted from Earth Drilling Ltd. of Calgary, Alberta. The rig was equipped with 150 mm diameter hollow stem augers. The geotechnical testpits were excavated on November 28, 2017. Tetra Tech's field representative for both programs was Mr. Stuart Smith.

Nine (9) boreholes (referenced as 17BH001 through 17BH009) were drilled to depths between 0.9 m and 2.2 m below existing ground level. It should be noted that due to auger refusal, all boreholes were terminated early and efforts, including relocating some boreholes (i.e., 17BH001, 17BH005, 17BH006, and 17BH007), were made to achieve the design borehole depths. From the boreholes, disturbed grab samples were obtained at select locations. In addition, Standard Penetration Tests (SPTs) were performed in select boreholes. Three (3) testpits (referenced as 17TP001, 17TP002, and 17TP003) were excavated to depths between 4.6 m and 5.3 m below ground level. All soil samples were visually classified in the field and the individual soil strata and the interfaces between them were noted. The borehole and testpit logs are presented in Appendix B. An explanation of the terms and symbols used on the logs is also included in Appendix B.

ISSUED FOR USE

FILE: ENG.LGEO03598-01

Via Email: Ischoening@mpe.ca

Slotted 25 mm diameter PVC standpipes were installed in the three testpit locations to monitor groundwater levels. The testpits were backfilled around the standpipes and the boreholes were backfilled with cuttings.

Classification tests, including grain size distribution, were performed in a laboratory on samples collected from the boreholes and testpits to aid in the determination of engineering properties. The results of the laboratory tests are presented in Appendix C, as well as included on the logs in Appendix B.

4.0 SUBSURFACE SOIL CONDITIONS

4.1 Soil Conditions

The general subsurface stratigraphy for the site comprised a surficial layer of topsoil, overlying sand or clay, overlying gravel, in turn underlain by bedrock.

Surficial topsoil was encountered at all borehole and testpit locations with thicknesses less than 300 mm. Sand, bordering on low to medium plastic clay, was present below the topsoil in 17TP002, 17TP003, and 17BH002; and extended to depths of between 0.9 m and 1.4 m below ground surface. The sand was described as silty, trace to some clay, trace to some gravel, damp, compact, and brown. The clay was described as silty, some sand to sandy, some gravel, damp, very stiff, low to medium plastic, and brown.

Gravel was encountered below the topsoil and/or sand and extended to depths of between 3.7 m and 4.9 m below ground surface. The gravel was described as sandy, some silt, trace clay, subrounded, well graded, sizes up to 400 mm, very dense, brown. The sand and gravel are considered alluvial in origin.

Bedrock was encountered below the gravel layer and extended to the termination depths of the testpits (due to excavator refusal). The bedrock was comprised of extremely week to very week conglomerate, sandstone, and siltstone.

4.2 Groundwater Conditions

At the time of drilling, no seepage was observed in any of the nine borehole locations and sloughing was only encountered in 17BH002. No seepage was observed in any of the testpit locations; however, sloughing of the granular material was generally encountered. All 25 mm PVC monitoring wells installed within the testpits were measured dry 7 days after drilling (December 5, 2017). It is expected that groundwater may be seasonal and may be directly related to the water elevations of the Castle River and Mill Creek.

5.0 SITE SUITABILITY ASSESSMENT

As discussed in Section 4.1, bedrock, including completely or highly weathered sandstone, siltstone, and conglomerate, was encountered at shallow depths ranging between 4.3 m and 5.1 m below the existing ground surface. The manual of "Design and Construction of Liners for Municipal Wastewater Stabilization Ponds" (by Alberta Environment and Sustainable Resource Development) can be used as a guideline for siting wastewater ponds, and is referenced in the "Standards and Guidelines for Municipal Waterworks, Wastewater and Storm Drainage Systems" (by the Alberta Government). In accordance with the requirement of Table 2.2 "Physical Site Criteria" in the manual it is noted that the bedrock encountered on this site does not meet the requirement that "A minimum depth of 10 m is recommended when the upper bedrock formation include coal seams, highly fractured or weathered rock, and other deposits with relatively high permeability."



According to Table 2.3 "Rating Chart for Physical Environmental Suitability of Site" in the manual, the suitability of this site was rated "low" for a lagoon development with the following facts:

- Completely to highly weathered sandstone bedrock is present with less than 10 m of overlying surficial sediments. – Low Suitability
- Alluvial sand and gravel are present as surficial sediments. Low Suitability
- Average topography of the area is unknown, but expected to be around 1%, with areas up to 5%. Medium Suitability

In addition, based on test results and Tetra Tech's experience of local soils, the low to medium plastic clay, only encountered at one borehole location, is not considered suitable as clay liner materials to meet seepage control criterion required by Alberta Environment and Sustainable Resource Development.

In conclusion, the site suitability for the proposed sanitary sewage lagoon development is considered low and site relocation is highly recommended. The geology, topography, and geomorphology of the site and surrounding area provide little assistance in mitigating environmental impacts of the proposed sanitary sewage lagoon.

6.0 LIMITATIONS OF REPORT

This report and its contents are intended for the sole use of MPE Engineering Ltd. and their agents. Tetra Tech Canada Inc. (Tetra Tech) does not accept any responsibility for the accuracy of any of the data, the analysis, or the recommendations contained or referenced in the report when the report is used or relied upon by any Party other MPE Engineering Ltd., or for any Project other than the proposed development at the subject site. Any such unauthorized use of this report is at the sole risk of the user. Use of this document is subject to the Limitations on Use of this Document attached in Appendix A or Contractual Terms and Conditions executed by both parties.

7.0 CLOSURE

We trust this report meets your present requirements. If you have any questions or comments, please contact the undersigned.

Respectfully submitted, Tetra Tech Canada Inc.

Prepared by:

Chris McRae, B.Sc., E.I.T.

Geotechnical Engineer-in-Training

Prairie Engineering Direct Line: 306.715.6121

Direct Line: 306.715.6121 chris.mcrae@tetratech.com

/tlp

Attachments: Appendix A: Limitations on Use of This Document

Appendix B: Borehole and Testpit Logs Appendix C: Laboratory Test Results

PERMIT TO PRACTICE

TETRA TECHICANADA INC.

Signature ,

December 13,2017

PERMIT NUMBER: P13774

The Association of Professional Engineers and Geoscientists of Alberta



Reviewed by:

Jiejun Zhao, P.Eng. Senior Geotechnical Engineer

Prairie Practice

Direct Line: 403.359.6513 jiejun.zhao@tetratech.com

APPENDIX A

LIMITATIONS ON USE OF THIS DOCUMENT



LIMITATIONS ON USE OF THIS DOCUMENT

GEOTECHNICAL

1.1 USE OF DOCUMENT AND OWNERSHIP

This document pertains to a specific site, a specific development, and a specific scope of work. The document may include plans, drawings, profiles and other supporting documents that collectively constitute the document (the "Professional Document").

The Professional Document is intended for the sole use of TETRA TECH's Client (the "Client") as specifically identified in the TETRA TECH Services Agreement or other Contractual Agreement entered into with the Client (either of which is termed the "Contract" herein). TETRA TECH does not accept any responsibility for the accuracy of any of the data, analyses, recommendations or other contents of the Professional Document when it is used or relied upon by any party other than the Client, unless authorized in writing by TETRA TECH.

Any unauthorized use of the Professional Document is at the sole risk of the user. TETRA TECH accepts no responsibility whatsoever for any loss or damage where such loss or damage is alleged to be or, is in fact, caused by the unauthorized use of the Professional Document.

Where TETRA TECH has expressly authorized the use of the Professional Document by a third party (an "Authorized Party"), consideration for such authorization is the Authorized Party's acceptance of these Limitations on Use of this Document as well as any limitations on liability contained in the Contract with the Client (all of which is collectively termed the "Limitations on Liability"). The Authorized Party should carefully review both these Limitations on Use of this Document and the Contract prior to making any use of the Professional Document. Any use made of the Professional Document by an Authorized Party constitutes the Authorized Party's express acceptance of, and agreement to, the Limitations on Liability.

The Professional Document and any other form or type of data or documents generated by TETRA TECH during the performance of the work are TETRA TECH's professional work product and shall remain the copyright property of TETRA TECH.

The Professional Document is subject to copyright and shall not be reproduced either wholly or in part without the prior, written permission of TETRA TECH. Additional copies of the Document, if required, may be obtained upon request.

1.2 ALTERNATIVE DOCUMENT FORMAT

Where TETRA TECH submits electronic file and/or hard copy versions of the Professional Document or any drawings or other project-related documents and deliverables (collectively termed TETRA TECH's "Instruments of Professional Service"), only the signed and/or sealed versions shall be considered final. The original signed and/or sealed electronic file and/or hard copy version archived by TETRA TECH shall be deemed to be the original. TETRA TECH will archive a protected digital copy of the original signed and/or sealed version for a period of 10 years.

Both electronic file and/or hard copy versions of TETRA TECH's Instruments of Professional Service shall not, under any circumstances, be altered by any party except TETRA TECH. TETRA TECH's Instruments of Professional Service will be used only and exactly as submitted by TETRA TECH.

Electronic files submitted by TETRA TECH have been prepared and submitted using specific software and hardware systems. TETRA TECH makes no representation about the compatibility of these files with the Client's current or future software and hardware systems.

1.3 STANDARD OF CARE

Services performed by TETRA TECH for the Professional Document have been conducted in accordance with the Contract, in a manner consistent with the level of skill ordinarily exercised by members of the profession currently practicing under similar conditions in the jurisdiction in which the services are provided. Professional judgment has been applied in developing the conclusions and/or recommendations provided in this Professional Document. No warranty or guarantee, express or implied, is made concerning the test results, comments, recommendations, or any other portion of the Professional Document.

If any error or omission is detected by the Client or an Authorized Party, the error or omission must be immediately brought to the attention of TETRA TECH.

1.4 DISCLOSURE OF INFORMATION BY CLIENT

The Client acknowledges that it has fully cooperated with TETRA TECH with respect to the provision of all available information on the past, present, and proposed conditions on the site, including historical information respecting the use of the site. The Client further acknowledges that in order for TETRA TECH to properly provide the services contracted for in the Contract, TETRA TECH has relied upon the Client with respect to both the full disclosure and accuracy of any such information.

1.5 INFORMATION PROVIDED TO TETRA TECH BY OTHERS

During the performance of the work and the preparation of this Professional Document, TETRA TECH may have relied on information provided by persons other than the Client.

While TETRA TECH endeavours to verify the accuracy of such information, TETRA TECH accepts no responsibility for the accuracy or the reliability of such information even where inaccurate or unreliable information impacts any recommendations, design or other deliverables and causes the Client or an Authorized Party loss or damage.

1.6 GENERAL LIMITATIONS OF DOCUMENT

This Professional Document is based solely on the conditions presented and the data available to TETRA TECH at the time the data were collected in the field or gathered from available databases.

The Client, and any Authorized Party, acknowledges that the Professional Document is based on limited data and that the conclusions, opinions, and recommendations contained in the Professional Document are the result of the application of professional judgment to such limited data.

The Professional Document is not applicable to any other sites, nor should it be relied upon for types of development other than those to which it refers. Any variation from the site conditions present, or variation in assumed conditions which might form the basis of design or recommendations as outlined in this report, at or on the development proposed as of the date of the Professional Document requires a supplementary investigation and assessment.

TETRA TECH is neither qualified to, nor is it making, any recommendations with respect to the purchase, sale, investment or development of the property, the decisions on which are the sole responsibility of the Client.



1.7 ENVIRONMENTAL AND REGULATORY ISSUES

Unless stipulated in the report, TETRA TECH has not been retained to investigate, address or consider and has not investigated, addressed or considered any environmental or regulatory issues associated with development on the subject site.

1.8 NATURE AND EXACTNESS OF SOIL AND ROCK DESCRIPTIONS

Classification and identification of soils and rocks are based upon commonly accepted systems and methods employed in professional geotechnical practice. This report contains descriptions of the systems and methods used. Where deviations from the system or method prevail, they are specifically mentioned.

Classification and identification of geological units are judgmental in nature as to both type and condition. TETRA TECH does not warrant conditions represented herein as exact, but infers accuracy only to the extent that is common in practice.

Where subsurface conditions encountered during development are different from those described in this report, qualified geotechnical personnel should revisit the site and review recommendations in light of the actual conditions encountered.

1.9 LOGS OF TESTHOLES

The testhole logs are a compilation of conditions and classification of soils and rocks as obtained from field observations and laboratory testing of selected samples. Soil and rock zones have been interpreted. Change from one geological zone to the other, indicated on the logs as a distinct line, can be, in fact, transitional. The extent of transition is interpretive. Any circumstance which requires precise definition of soil or rock zone transition elevations may require further investigation and review.

1.10 STRATIGRAPHIC AND GEOLOGICAL INFORMATION

The stratigraphic and geological information indicated on drawings contained in this report are inferred from logs of test holes and/or soil/rock exposures. Stratigraphy is known only at the locations of the test hole or exposure. Actual geology and stratigraphy between test holes and/or exposures may vary from that shown on these drawings. Natural variations in geological conditions are inherent and are a function of the historic environment. TETRA TECH does not represent the conditions illustrated as exact but recognizes that variations will exist. Where knowledge of more precise locations of geological units is necessary, additional investigation and review may be necessary.

1.11 PROTECTION OF EXPOSED GROUND

Excavation and construction operations expose geological materials to climatic elements (freeze/thaw, wet/dry) and/or mechanical disturbance which can cause severe deterioration. Unless otherwise specifically indicated in this report, the walls and floors of excavations must be protected from the elements, particularly moisture, desiccation, frost action and construction traffic.

1.12 SUPPORT OF ADJACENT GROUND AND STRUCTURES

Unless otherwise specifically advised, support of ground and structures adjacent to the anticipated construction and preservation of adjacent ground and structures from the adverse impact of construction activity is required.

1.13 INFLUENCE OF CONSTRUCTION ACTIVITY

There is a direct correlation between construction activity and structural performance of adjacent buildings and other installations. The influence of all anticipated construction activities should be considered by the contractor, owner, architect and prime engineer in consultation with a geotechnical engineer when the final design and construction techniques are known.

1.14 OBSERVATIONS DURING CONSTRUCTION

Because of the nature of geological deposits, the judgmental nature of geotechnical engineering, as well as the potential of adverse circumstances arising from construction activity, observations during site preparation, excavation and construction should be carried out by a geotechnical engineer. These observations may then serve as the basis for confirmation and/or alteration of geotechnical recommendations or design guidelines presented herein.

1.15 DRAINAGE SYSTEMS

Where temporary or permanent drainage systems are installed within or around a structure, the systems which will be installed must protect the structure from loss of ground due to internal erosion and must be designed so as to assure continued performance of the drains. Specific design detail of such systems should be developed or reviewed by the geotechnical engineer. Unless otherwise specified, it is a condition of this report that effective temporary and permanent drainage systems are required and that they must be considered in relation to project purpose and function.

1.16 BEARING CAPACITY

Design bearing capacities, loads and allowable stresses quoted in this report relate to a specific soil or rock type and condition. Construction activity and environmental circumstances can materially change the condition of soil or rock. The elevation at which a soil or rock type occurs is variable. It is a requirement of this report that structural elements be founded in and/or upon geological materials of the type and in the condition assumed. Sufficient observations should be made by qualified geotechnical personnel during construction to assure that the soil and/or rock conditions assumed in this report in fact exist at the site.

1.17 SAMPLES

TETRA TECH will retain all soil and rock samples for 30 days after this report is issued. Further storage or transfer of samples can be made at the Client's expense upon written request, otherwise samples will be discarded.



APPENDIX B

BOREHOLE AND TESTPIT LOGS



TERMS USED ON BOREHOLE LOGS

TERMS DESCRIBING CONSISTENCY OR CONDITION

COARSE GRAINED SOILS (major portion retained on 0.075mm sieve): Includes (1) clean gravels and sands, and (2) silty or clayey gravels and sands. Condition is rated according to relative density, as inferred from laboratory or in situ tests.

DESCRIPTIVE TERM	RELATIVE DENSITY	N (blows per 0.3m)
Very Loose	0 TO 20%	0 to 4
Loose	20 TO 40%	4 to 10
Compact	40 TO 75%	10 to 30
Dense	75 TO 90%	30 to 50
Very Dense	90 TO 100%	greater than 50

The number of blows, N, on a 51mm 0.D. split spoon sampler of a 63.5kg weight falling 0.76m, required to drive the sampler a distance of 0.3m from 0.15m to 0.45m.

FINE GRAINED SOILS (major portion passing 0.075mm sieve): Includes (1) inorganic and organic silts and clays, (2) gravelly, sandy, or silty clays, and (3) clayey silts. Consistency is rated according to shearing strength, as estimated from laboratory or in situ tests.

DESCRIPTIVE TERM	UNCONFINED COMPRESSIVE
	STRENGTH (KPA)
Very Soft	Less than 25
Soft	25 to 50
Firm	50 to 100
Stiff	100 to 200
Very Stiff	200 to 400
Hard	Greater than 400

NOTE: Slickensided and fissured clays may have lower unconfined compressive strengths than shown above, because of planes of weakness or cracks in the soil.

GENERAL DESCRIPTIVE TERMS

Slickensided - having inclined planes of weakness that are slick and glossy in appearance.

Fissured - containing shrinkage cracks, frequently filled with fine sand or silt; usually more or less vertical.

Laminated - composed of thin layers of varying colour and texture.

Interbedded - composed of alternate layers of different soil types.

Calcareous - containing appreciable quantities of calcium carbonate.:

Well graded - having wide range in grain sizes and substantial amounts of intermediate particle sizes.


Poorly graded - predominantly of one grain size, or having a range of sizes with some intermediate size missing.

Data presented hereon is for the sole use of the stipulated client. Tetra Tech EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA. The testing services reported herein have been performed to recognized industry standards, unless noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.



D

					MOD	IFIED UNIFIEI	O SOIL	CL	ASSII	FICAT	ION								
МА	JOR DIVIS	ON		GROUP SYMBOL		TYPICAL DESCRIPTION				LABO	RATORY	CLASS	IFICATIO	N CRIT	TERIA				
	uo e	3	3	GW		graded gravels and grave mixtures, little or no fine			on symbols	$C_v = D_{ee}$ $C_c = \overline{D}$			eater tha						
	ELS coarse fracti 75 mm sieve	CLEAN	GRAN	GP		y graded gravels and gra mixtures, little or no fine			GW, GP, SW, SP GM, GC, SM, SC Borderline Classification requiring use of dual symbols	Not me	eting bot	h criteria	for GW						
n sleve*	GRAVELS 50% or more of coarse fraction retained on 4.75 mm sleve	ELS H	S	GM		gravels, Il-sand-silt mixtures		of fines	GM, GC, GM, GC, Borderli requiring	Atterberg limits plot below "A" line or plasticity index less than 4			18	plottin hatche	d area				
INED SOILS led on 75 µr	50% rel	GRAVELS	NE -	GC		y gravels, il-sand-clay mixtures		of percentage			g limits Icity inde				requir	ine ications ing use ymbols			
COARSE-GRAINED SOILS More than 50% retained on 75 µm sieve*	ewe	AN	Sa	SW		graded sands and gravel s, little or no fines	lly	Classification on basis of percentage of fines	Lisieve musieve leve	$C_{c} = D_{cc}$ $C_{c} = \overline{D}$			eater that						
More than	SANDS More than 50% of coarse fraction passes 4.75 mm sieve	CLEAN	SAN	SP		y graded sands and grav s, little or no fines	elly	Classifica	Less than 5% Pass 75 mµsleve More than 12% Pass 75 mµsleve 5% to 12% Pass 75 µm sleve	Not me	ating bot	h criteria	a for SW						
	SANDS fore than 50% of tion passes 4.7	IDS TH	83	SM	Silty	sands, sand-slit mixtures	3		More than 5 More than 1 5% to 12%		rg limits icity Inde			10	plottin	ed area			
	M	SANDS	Æ	sc	Claye	y sands, sand-clay mbdu	ires		`		rg limits icity inde				classi requir	fications ing use ymbols			
	SILTS	Bmit	<50	ML	rock	anic slits, very fine sand flour, slity or clayey fine s ght plasticity		For cla	ssification	of fine-gra			action of		rained so	ils.			
C*	SII	Uquid Bmit	>50	МН	diato	anic sitts, micaceous or maceous fine sands or elastic sitts		80	Soils pas	sing 425 µm		PLAOTIO	T						
FINE-GRAINED SOILS (by behavior) 50% or more passes 75 µm sleve*	asticity ic content	nic content		CL	grave	anic clays of low plastici ally clays, sandy clays, clays, lean clays	ty,	50 ₩ 40	Equation o	f "A" line: P1 =	0.73 (11 - 20)			СН					
ED SOILS e passes	CLAYS Above "A" line on plasticity chart negligible organic content	Liquid limit	Uquid limit 30-50 <30	CI		anic clays of medium icity, slity clays		STICITY IND	PLASTICITY INDEX					"K We					
INE-GRAIN	Above chart neg	chart neglig		chart negli		СН		anic clays of high icity, fat clays		₽ 20 10		CL.				МН	or OH		
L 47	ORGANIC SILTS AND CLAYS	Liquid limit	95	OL		nic slits and organic slity w plasticity	clays	7 4 0		20 EN 10	30 M	L or OL		80	70	10	0 :		
	ORGAN	Liquid	>20	ОН		nic clays of medium gh plasticity				LIQUID LIMIT									
HIGHLY ORGANIC SOILS PT Peat and other highly organic soils								Refe	*Based on the material passing the 75 mm sleve Reference: ASTM Designation D2487, for identification proced see D2488. USC as modified by PFRA							re			
					SOIL COMPO	DNENTS						OVE	RSIZE MA	ATERIAL					
FR	ACTION			SIEVE SIZE		DEFINING R PERCENTAGE MINOR COM	BY MASS 0	F		Rounde	i or subr		to 300	mm					
			F	PASSING RE	ETAINED	PERCENTAGE	DESCR	IPTOR		BOULDE	RS	> 300	mm						
GRAVEL coarse 75 mm fine 19 mm					19 mm 4.75 mm	>35 % 21 to 35 %	"an			Not rous	ded RAGMEN	rs		'5 mm 0.76 cu	blc met	re in vo	ume		
medłum 2			2.0	00 mm	2.00 mm 425 µm 75 µm	10 to 20 %	10 to 20 % "som												
or	non plastic)			75 µm		as abo													





BOREHOLE KEYSHEET

Water Level Measurement

Measured in standpipe, piezometer or well



Inferred

Sample Types

A-Casing





Disturbed, Bag, Grab



HQ Core



Jar and Bag



NQ Core



No Recovery



Split Spoon/SPT



Backfill Materials



Asphalt



Bentonite



Cement/



Drill Cuttings



Gravel



Sand



Topsoil Backfill

Lithology - Graphical Legend¹



Asphalt



Bedrock



Cobbles/Boulders



Clay



Coal



Concrete





Gravel



Limestone



Mudstone

Organics

Peat

Sand



Sandstone



Shale

Silt

Siltstone

TIII

Topsoil

^{1.} The graphical legend is an approximation and for visual representation only. Soil strata may comprise a combination of the basic symbols shown above. Particle sizes are not drawn to scale



			Borehole No: 17BH00	11/	4		
M	PE	ENGINEERING LTD.	Project: BEAVER MINES SANITARY LAGOON	Proje	ct No: I	ENG.LGE003598-01	
	_		Location: LSD 2-19-6-1 W5M				
			NEAR BEAVER MINES, AB I N: 5485004, E: 708546	PRO.	JECT E	NGINEER: CHRIS MCRAE	
Oepth (m)					Moisture Content (%)	Plastic Moisture Liqui Limit Content Limi 20 40 60 80	th (f)
	Hollow Stem Auger	GRAVEL - sandy, silty, trace clay, sub rounded, well graduate in the size of the sandy and silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty, trace clay, sub rounded, well graduate in the sandy silty silty, trace clay, sub rounded, well graduate in the sandy silty silty silty, trace clay, sub rounded, well graduate in the sandy silty silt	aded, sizes to 75 mm, damp, dense to very dense, brown				2-
2		No Seepage or Sloughing Upon Completion No Standpipe Installed					5
3		TETRA TECH	Contractor: CHILAKO DRILLING SERVICES LTD. Drilling Rig Type: 150mm HOLLOW STEM AUGER	_		Depth: 0.91 m 2017 November 07	9-
П	lt	TETRATECH	Logged By: SS	-		Date: 2017 November 07	
	_	J	Reviewed By: JZ	-	1 of 1		
FOTEC	HNICA	N. ENG-LGE003598-01 BEAVER MINES SANITARY LAGOON.GPJ EBA.GD		30			

Borehole No: 17BH001B MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGE003598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485005, E: 708543 PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Depth (m) Method Soil Description Plastic Moisture Liquid Limit Content Limit 40 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 75 mm, damp, dense to very dense, brown ... sizes to >150 mm, very dense, auger refusal 3-End of Borehole @ 0.9 m - 1 No Seepage or Sloughing Upon Completion No Standpipe Installed 5-6 2 7-8-9-Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 0.91 m **TETRA TECH** Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 Logged By: SS Completion Date: 2017 November 07 Reviewed By: JZ Page 1 of 1

GEOTECHNICAL ENG-LGE003598-01 BEAVER MINES SANITARY LAGOON.GPJ EBA.GDT 17/12/11

			Borehole No: 17BH0	0	1	3				
M	PE	ENGINEERING LTD.	Project: BEAVER MINES SANITARY LAGOON				ENG.LGE	003598-01		
			Location: LSD 2-19-6-1 W5M							
			NEAR BEAVER MINES, AB 1 N: 5485005, E: 70854	0	PROJ	ECT E	NGINEE	R: CHRIS N	CRAE	
Depth (m)	Method	Des	Soil scription	Sample Type	Sample Number	Moisture Content (%)	Plastic Limit I– 20	Moisture Content 40 60	Liquid Limit 1	Depth (ft)
U		TOPSOIL - clay, sandy, silty, trace gravel, moist, dark b	orown, roote, organics					: :	:	
-		GRAVEL - sandy, silty, trace day, sub rounded, well gra	aded, sizes to 75 mm, damp, dense to very dense, brown		B1					1-
- - 1		sizes to >150 mm, very dense, auger refusal End of Borehole @ 0.9 m								- 3-
- - -		No Seepage or Sloughing Upon Completion No Standpipe Installed								5-
- 2										7-
										9-
3			Contractor: CHILAKO DRILLING SERVICES LTD.	_	Com	pletion	Depth: 0.	01 m		
C		7	Drilling Rig Type: 150mm SOLID STEM AUGER		_			ember 07		-
	R	TETRATECH	Logged By: SS					17 Novemb	er 07	
	_		Reviewed By: 17			1 of 1	Jul. 20	I TOTGIND	01 01	

Borehole No: 17BH002 MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485119, E: 708622 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) ◆ DCPT (N) ◆ 80 Sample Number Sample Type SPT (N) Depth (m) Method Depth (ft) Soil SPT (N) 40 60 80 Description Plastic Moisture Liquid Limit Content Limit 20 40 60 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, CLAY - silty, some sand to sandy, some gravel, damp, very stiff, low to medium plastic, brown, roots 2 3-GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 50 mm, damp, dense, brown 5 D1 47 6 2 50 ... sizes to > 100 mm, auger refusal End of Borehole @ 2.2 m 8 No Seepage, Soughing to 0.9 m Upon Completion No Standpipe Installed 9 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 2.21 m Drilling Rig Type: 150mm SOLID STEM AUGER Start Date: 2017 November 07 **TETRA TECH** Tolder, BA: 22 Completion Date: 2017, November 07 Reviewed By: JZ Page 1 of 1

Borehole No: 17BH003 MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGE003598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485009, E: 708597 PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Sample Number Sample Type SPT (N) Depth (m) Method Soil Depth (ft) Description Plastic Moisture Liquid Limit Content Limit 20 40 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 75 mm, damp to moist, dense, brown 3 >100 D1 50 ... very dense, auger refusal 120mm End of Borehole @ 1.2 m No Seepage or Sloughing Upon Completion 5-No Standpipe Installed 6-- 2 8-9-Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 1.23 m Drilling Rig Type: 150mm HOLLOW STEM AUGER **TETRA TECH** Start Date: 2017 November 07 Completion Date: 2017 November 07 Logged By: SS Reviewed By: JZ Page 1 of 1

GEOTECHNICAL ENG-LGE003598-01 BEAVER MINES SANITARY LAGOON.GPJ EBA.GDT 17/12/11

Borehole No: 17BH004 MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGE003598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485094, E: 708528 PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Sample Number Sample Type SPT (N) Depth (m) Method Soil Description Plastic Moisture Liquid Limit Limit Content 20 40 60 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 75 mm, damp, dense, brown 3-...100 mm very moist pocket, gravel sizes to 100 mm, very dense ... moist D1 54 6-... auger refusal End of Borehole @ 1.9 m 2 No Seepage or Sloughing Upon Completion No Standpipe Installed 8-Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 1.9 m **TETRA TECH** Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 Logged By: SS Completion Date: 2017 November 07 Reviewed By: JZ Page 1 of 1

Borehole No: 17BH005A MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No. ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485148, E: 708542 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Depth (m) Method Soil Description Plastic Moisture Liquid Limit Limit Content 80 40 TOPSOIL - clay, sandy, slity, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 75 mm, damp, dense, brown ... sizes to > 150 mm, auger refusal End of Borehole @ 0.3 m No Seepage or Slouhging Upon Completion No Standpipe Installed 2-3-6 - 2 9 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 0.3 m **TETRA TECH** Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 Logged By: SS Completion Date: 2017 November 07

Reviewed By: JZ.

Page 1 of 1

Borehole No: 17BH005B MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB - [N: 5485150, E: 708538 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Sample Number SPT (N) Depth (m) Method Soil Description Plastic Moisture Liquid Limit Content Limit 60 40 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace clay, sub rounded, well graded, sizes to 75 mm, damp, dense, brown ... sizes to > 100 mm, very dense 3 77 .. auger refusal End of Borehole @ 1.4 m 5-No Seepage or Sloughing Upon Completion No Standpipe Installed 2 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 1.4 m **TETRA TECH** Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 Logged By: SS Completion Date: 2017 November 07 Reviewed By: JZ Page 1 of 1

GEOTECHNICAL ENG-LGE003598-01 BEAVER MINES SANITARY LAGOON.GPJ EBA.GDT 17/12/11

Borehole No: 17BH006A MPE ENGINEERING LTD. Project BEAVER MINES SANITARY LAGOON Project No: ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB / N: 5485141, E: 708472 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Depth (m) Method Soil (ft) Description Plastic Moisture Liquid Content Limit 20 40 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace clay, sub rounded, well graded, sizes to 75 mm, damp, dense, brown ... sizes to > 100 mm, auger refusal End of Borehole @ 0.3 m 2-No Seepage or Slouhging Upon Completion No Standpipe Installed 3-5 6-2 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 0.3 m **TETRA TECH** Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 Logger By: SS Completion Date: 2017, November 07 Reviewed By: JZ Page 1 of 1

GEOTECHNICAL ENG-LGE003598-01 BEAVER MINES SANITARY LAGOON GPJ EBA GDT 17/12/11

Borehole No: 17BH006B MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485144, E: 708474 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Sample Number Sample Type SPT (N) Depth (m) Method Soil Depth (#) Description Plastic Moisture Liquid Limit Content Limit 40 60 80 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace clay, sub rounded, well graded, sizes to 75 mm, damp, dense, brown ... sizes to > 100 mm, dense to very dense 3-**D1** 49 .. auger refusal End of Borehole @ 1.4 m No Seepage or Sloughing Upon Completion No Standpipe Installed 2 8 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 1.4 m Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 **TETRA TECH** Logged By: SS Completion Date: 2017, November 07

Reviewed By: JZ

Page 1 of 1

			Borehole No: 17BH00)	4							
M	PE	ENGINEERING LTD.	Project: BEAVER MINES SANITARY LAGOON	Projec	ct No: ENG.LGE003598-01							
			Location: LSD 2-19-6-1 W5M									
			NEAR BEAVER MINES, AB I N: 5485239, E: 708469	PRO.	ECT E	NGINEE	R: CHRIS M	ICRAE				
Depth (m)	Method	TOPSOIL - clay, sandy, silty, trace gravel, moist, dark to	Soil Description		Moisture Content (%)	Plastic Limit 1- 20	Moisture Content	Liquid Limit I 80	Depth (ft)			
		GRAVEL - sandy, silty, trace clay, sub rounded, well gr	aded, sizes to 150 mm, moist, very dense, brown									
		auger refusal		/	1		1 -	,	1-			
		End of Borehole @ 0.3 m										
		No Seepage or Sloughing Upon Completion No Standpipe Installed							2-			
1									3			
									4			
									5-			
									6			
- 2												
									7-			
									8-			
									9			
3			Contractor: CHILAKO DRILLING SERVICES LTD.	Come	oletion	Depth: 0.	3 m					
		TETRATECH	Drilling Rig Type: 150mm HOLLOW STEM AUGER			2017 Nov						
П	t	, ILIKA IECH	Logged By: SS				7 November	ar 0,7				
_		N. ENG-LGE003598-11 BEAN FER MINES SANITARY LAGOON.GPJ EBA.G	Reviewed By: JZ	Page	1 of 1							

Borehole No: 17BH007B MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No. ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB | N: 5485234, E: 708469 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Sample Number Sample Type Depth (m) Soil Description Plastic Moisture Liquid Limit Content Limit 20 40 60 80 0 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 150 mm, moist, very dense, brown >100 D1 50 2-.. auger refusal (Omm) End of Borehole @ 0.6 m 3-No Seepage or Slouhging Upon Completion No Standpipe Installed 6-- 2 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 0.6 m **TETRA TECH** Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 Logged By: SS Completion Date: 2017 November 07 Reviewed by: JZ Page 1 of 1

GEOTECHNICAL ENG-LGE003588-01 BEAVER MINES SANITARY LAGOON.GPJ EBA.GDT 17/12/11

Borehole No: 17BH008 MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGE003598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485281, E: 708562 PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) Sample Number Sample Type SPT (N) Depth (m) Method Soil Description Plastic Moisture Liquid Limit Content Limit 40 60 80 0 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, organics GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 100 mm, moist, very dense, brown 2->100 ... sizes to > 100 mm, auger refusal D1 50 20mm End of Borehole @ 0.9 m No Seepage or Sloughing Upon Completion, No Standpipe Installed 6-2 Contractor: CHILAKO DRILLING SERVICES LTD. Completion Depth: 0.92 m Drilling Rig Type: 150mm HOLLOW STEM AUGER Start Date: 2017 November 07 **TETRA TECH** Logged By: SS Completion Date: 2017 November 07 Reviewed By: JZ Page 1 of 1

GEOTECHNICAL ENG-LGE003598-01 BEAVER MINES, SANITARY, LAGLON, GPJ EBA. GDT. 17/1/2/11

Borehole No: 17BH009 MPE ENGINEERING LTD. Project: BEAVER MINES SANITARY LAGOON Project No: ENG.LGEO03598-01 Location: LSD 2-19-6-1 W5M NEAR BEAVER MINES, AB I N: 5485036, E: 708442 | PROJECT ENGINEER: CHRIS MCRAE Moisture Content (%) ◆ DCPT (N) ◆ 80 40 60 80 Sample Number DCPT (N) SPT (N) Depth (m) Method Soil Depth (ft) SPT (N) 40 60 80 Description Plastic Moisture Liquid Content Limit 80 20 40 60 TOPSOIL - clay, sandy, silty, trace gravel, moist, dark brown, roots, GRAVEL - sandy, silty, trace day, sub rounded, well graded, sizes to 50 mm, damp to moist, dense, brown 3-... sizes to 75 mm, moist, very dense ... sizes to > 100 mm, auger refusal D1 41 5-34 ... dense 6 16 2 15 End of Borehole @ 2.1 m No Seepage or Soughing Upon Completion. 8 No Standpipe Installed 9



	Contractor: CHILAKO DRILLING SERVICES LTD.	Completion Depth: 2.1 m
	Drilling Rig Type: 150mm HOLLOW STEM AUGER	Start Date: 2017 November 07
1	Logged By: SS	Completion Date: 2017. November 07
1	Reviewed By: JZ	Page 1 di 1

			Borehole No: 17TI	P(00	1							
М	Þ	ENGINEERING LTD.	Project: BEAVER MINES SANITARY LAGOON			Project No: ENG.LGEO03598-01							
			Location: LSD 2-19-6-1 W5M										
			NEAR BEAVER MINES, AB I N: 5485003, E:	708	554	PROJ	ECT ENC	SINEER: C	HRIS MCF	AE			
O Depth	Method	Desci	oil ription	Sample Type	Sample Number	Moisture Content (%)	Plastic Limit I– 20	Moisture Content 40 60	Liquid Limit -I 80		Depth (ft)		
-		TOPSOIL - clay, sandy, silty, trace gravel, moist, dark be	own, roots, organics										
		GRAVEL - some sand, some silt, trace clay, sub rounde trace root hairs sandy, silty, damp to moist, very moist sandy silt lens			B1						1 2 3 4 4 5 10 11 12 13 13 13 13 13 13 13 13 13 13 13 13 13		
-		SANDSTONE - extremely weak, greyish brown, complete	ely to highly weathered						:		14-		
5		trace seepage very weak to weak, grey, moderately weathered, exceeding from 5.2 m, Sloughing to 4.3 m Upon Completed Slotted 25 mm PVC Standpipe Installed to 4.3 m Test Pit Measured Dry on Dec. 5, 2017	vator refusal		B2						15 16 17 18 19 20 21		
7													
			Contractor: PAT DWYER					pth: 5.3 m					
	Ţ.	TETRATECH	Drilling Rig Type: EXCAVATOR			├		7 November					
(•)	Logged By: SS			· · · · · · · · ·		te: 2017 No	ovember 2	8			
-			Reviewed Bv: JZ			Page	1 of 1						

MP	E ENGINEERING LTD.	Project: BEAVER MINES SANITARY LAGOON Location: LSD 2-19-6-1 W5M			Droine	AN- FNOLO	250005	00.04											
			Project: BEAVER MINES SANITARY LAGOON							Project No: ENG.LGE003598-01									
		NEAR BEAVER MINES, AB I N: 5485109, E:	708	623	PROJ	ECT ENGINE	FR: CH	IRIS MCI	RAE										
		11.0100100, 21		020	11100	LOT LITORILE	L O		_										
(m)	S Desc	oil ription	Sample Type	Sample Number	Moisture Content (%)		pisture pontent	Liquid Limit -1 80	П	Depth (ft)									
	TOPSOIL - clay, sandy, silty, trace gravel, moist, dark b	rown, roots, organics				: :	:	:											
	SAND - silty, trace to some clay, damp, compact, brown	n, roots		B1			6 9 6 6 6 6			1-									
-1	GRAVEL - some sand, some silt, trace clay, sub rounde brown	ed, well graded, sizes to 200 mm, damp, very dense,		B2						1- 2- 3- 4- 5- 6- 7- 8- 10-									
- 2										5- 6-									
-	sandy, silty, damp to moist									8-									
- 3										10- 11- 12-									
- 4	CONGLOMERATE - extremely weak, brown, completel	y to highly weathered		B3						13-									
	SANDSTONE - extremely weak to very weak, grey, high	nly weathered	+		-	: :	:	:		15-									
- 5	End of Test Pit @ 4.6 m No Seepage, Sloughing to 3.7 m Upon Completion Slotted 25 mm PVC Standpipe Installed to 3.7 m Test Pit Measured Dry on Dec. 5, 2017				or control of					16- 17- 18-									
- 6										19-									
										21-									
7		Contractor: PAT DWYER			Come	letion Donth	16m												
	TETRA 75.00		Completion Depth: 4.6 m Start Date: 2017 November 28																
T	E TETRA TECH	Drilling Rig Type: EXCAVATOR Logged By: SS																	
		Reviewed By: JZ	Completion Date: 2017 November 28 Page 1 of 1																

			Borehole No: 17TI	7	JU	3							
ИP	E	ENGINEERING LTD.	Project: BEAVER MINES SANITARY LAGOON			Project No: ENG.LGEO03598-01							
			Location: LSD 2-19-6-1 W5M										
			NEAR BEAVER MINES, AB I N: 5485101, E:	708	520	PROJ	ECT ENGINEER: CH	RIS MCRAE					
(m)			oil ription rown, roots, organics	Sample Type	Sample Number	Moisture Content (%)	Plastic Moisture Limit Content 20 40 60	Liquid Limit -1 80	Depth				
		SAND - silty, trace to some clay, trace to some gravel, of GRAVEL - some sand, some silt, sub rounded, well grades			B1								
		sandy											
		SAND - silty, trace clay, trace gravel, fine grained, well g trace clay lenses to 10 mm SILTSTONE - extremely weak, brown, completely weath very weak to weak, dark blueish grey, moderately to h End of Test Pit @ 5.3 m			B2 B3								
		No Seepage, Sloughing to 4.3 m Upon Completion Slotted 25 mm PVC Standpipe Installed to 4.3 m Test Pit Measured Dry on Dec. 5, 2017	Contractor: PAT DWYER			Como	oletion Depth: 5.5 m						
		•		Start Date: 2017 November 28									
		TETDATECH	Drilling Rig Type: EXCAVATOR			Start I	Date: 2017 November	28					
1	t	TETRATECH	Drilling Rig Type: EXCAVATOR Logged By: SS	_			Date: 2017 November Detion Date: 2017 Nov						

APPENDIX C LABORATORY TEST RESULTS



AGGREGATE ANALYSIS REPORT

PROJECT: Beaver Mines Sanitary Lagoon SAMPLE NUMBER: 17TP001

PROJECT NUMBER: ENG.LGE003598 DATE SAMPLED: 11-Dec-17

CLIENT: MPE Engineering Ltd. BY: TT

ATTENTION. TIME: N/A

DESCRIPTION: TWO OR MORE FRACTURED FACES: N/A

LOCATION: MOISTURE CONTENT: N/A


PERCENT PASSING SIEVE SIZE

SIEVE SIZE (mm)	500	400	300	250	200	150	100	75	50	40	30	25	20	10	5
UPPER LIMIT															
LOWER LIMIT															
TEST RESULT					100	84	64	50	45	44	44	44.0	33.0	26.0	20.0

REMARKS: Sample Size: 32.46 kg

Sample above 5 mm, See corresponding grain size distribution for REVIEWED BY: _______ C.E.T.

passing 5 mm.



Data presented hereon is for the sole use of the stipulated client. Tetra Tech EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of Tetra Tech EBA. The testing services reported herein have been performed to recognized industry standards, unless noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, Tetra Tech EBA



PARTICLE SIZE ANALYSIS REPORT ASTM C136 & C117 Sieve Size Percent Passing (mm) 50.000 #N/A Project: Beaver Mines Sanitary Lagoon #N/A 37.500 Project Number: ENG.LGE003598-01 25.000 #N/A #N/A December 11, 2017 19.000 Date Tested: 12.500 #N/A Borehole Number: 17TP001 9.500 100 Depth: 0.3 m Soil Description: 4.750 98 2.000 67 Cu: Cc: 0.850 44 0.425 27 Not done Natural Moisture Content: Remarks: See corrisponding sample for for sample larger than 5 mm. 0.250 16 0.150 9 2.4 0.075 Sand Gravel Clay Silt




Data presented hereon is for the sole use of the stipulated client. Tetra Tech is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of Tetra Tech. The testing services reported herein have been performed to recognized industry standards, unless noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, Tetra Tech will provide it upon written request.



PARTICLE SIZE ANALYSIS (Hydrometer) TEST REPORT


ASTM D422

Project: Beaver Mines Sanitary Lagoon Sample No.: N/A Client: MPE Engineering Borehole/ TP: 17TP002 Project No.: 704-ENG.LGEO03598 Depth: 0.3 m Location: **Date Tested** December 11, 2017 Description **: SAND - Silty, some clay Tested By: PL



Remarks: * The upper clay size of 2 µm is as per the Canadian Foundation Manual.

Reviewed By: P.Eng.





^{**} The description is behaviour based & subject to EBA description protocols.